

Sea-Container Side Wall

Typical Seatainer Plan View

100 x 100 x 6 x 200 long angle bracket site welded to shop welded cap-plate & seatainer corner lock-downs or side rail frames. 6mm CFW top & bottom webs.

Sea-Container Door End View

Number of screw-piles and fixing location subject to size of seatainer ground and wind loading conditions.

Floor & Under-Frame

GL

Cyclonic Trans/Bld Screw-piles. Code: (Nom. SP76x5 or SP89x5.5)

Detail Plan View

Generic Cap-Plated Screw-pile to Sea-Container Interface Connection

© Copywrite October 2008[®] Drawing No. SL20082008

